Notification dated 25th March 1929.

It is hereby notified for general information of the public that the timber described below were found lying unclaimed in the District jungles of Jade and Mangapur villages, Sorab Taluk.

Any person having any claim to these logs may present a written statement of such claim to the District Forest Officer, Sagar Division, within one month from the date of the publication of this notification, and establish the same to the satisfaction of the above Officer, failing which, the ownership of the timber shall vest in Government under section 42 of the Mysore Forest Regulation.

The logs from serial Nos. 1 to 6 are now lying in the custody of the Patel Jade village and logs from serial Nos. 7 to 11 in the custody of Kavi Siddanna of Mangapur Village :—

Taluk, Hobli and Village	Range		Kind of log	Measurement of log L.	G.	C.ft.	Remarks
Jade Village Survey No. 130 ..	Sorab ..	1	Teak Rd. ..	17—4	3—9	15	These logs bear no marks and numbers.
		2	Do ..	10—3	3—4	7	
		3	Do ..	16—9	3—7	13	
		4	Do ..	16—6	3—4	11	
Do do 168 ..	Do ..	5	Do ..	10—0	2—9	5	
		6	Do ..	8—2	2—6	3	
Mangapur District Forest ..	Do ..	7	Do ..	9—9	2—0	2	
		8	Do ..	8—0	2—5	3	
		9	Do ..	15—7	2—9	7	
		10	Do ..	9—3	2—4	3	
		11	Do ..	8—9	2—2	3	
	Total ..	11				72 C.ft.	

B. MADHAVA RAO,
District Forest Officer.

MYSORE DIVISION.

Dated 20th March 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 3 P.M., 15th April 1929, for Restoring Madalahalli Tank of Mullukatte Village, Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division, Mysore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 (Two hundred and fifty only) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Madalahalli Tank, Nagamangala Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work clearly.

Abstract estimate for Restoring Madalahalli Tank Reg. Number of Mullukatte Village Nagamangala Taluk.

No.	Details of work	Per	Quantity
	I Bund.		
1	Clearing jungle on bund	Lump	sum
2	Cutting steps and grips whereever new bund is put up ...	Lump	sum
3	Earthwork to bund with watering and tamping, etc., complete	C.yd.	19,186
4	Turfing to slopes	Sqr.	781·04
5	Gravel backing to rough stone revetment with one mile lead ...	C.yd.	1,382
6	Rough stone work new with jelly backing	„	2,384
7	Rough stone work old removing and resetting the same with new jelly (as per details in separate statement attached).	„	185
8	Providing and fixing grade stones including cutting figures and painting.	No.	29
9	Providing and fixing index stones	„	29
10	Providing and fixing guage stone with cutting figures and painting, etc.	„	1
11	Providing and fixing Register No. and date stone with figuring and painting.	„	1
	Providing B. M. stone with figuring and painting... ...	„	2
	Sluice.		
1	Clearing site and levelling ground	Lump	sum
2	Benching rock	Lump	sum
3	Earthwork excavating foundation	C.yd.	9
4	Concrete in surki mortar	C.ft.	183
5	Burnt brick in surki mortar	„	534
6	Burnt stone slabs 6″ thick dressed and fixed in surki mortar ...	S.ft.	240
7	Surki plastering	Sqr.	7·84
8	Cutting holes in guide and orifice slabs	No.	4
9	Providing wooden plug with iron rod and locking arrangement	Lump	sum
	III Breach.		
1	Clearing sand silt, etc., from the breach	C.yd.	444
2	Earthwork excavating foundation in mixed soil	„	40
3	Blastering rock	Lump	sum
4	Benching rock for core wall	S.ft.	672
5	Burnt brick in surki mortar	C.ft.	630
6	Plastering with surki mortar	Sqr.	9.81
7	Puddle	C.yd.	238
8	Earthwork filling in the breach with a mixture of $\frac{1}{3}$ good gravel and $\frac{2}{3}$ clay including watering and tamping and consolidating, etc., complete.	„	3,259
9	Turfing to slopes	Sqr.	47·61
10	Gravel backing to revetment with one mile lead	C.yd.	148
11	Rough stone revetment new jelly backing	„	283
	IV Left Waste weir.		
1	Earthwork excavating foundation and draft and approach clearing	C.yd	2082
2	Concrete in surki mortar	C.ft.	687
3	Burnt brick in surki mortar	„	1,278
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar ...	S.ft.	590
5	Surki plastering	Sqr.	21·58
6	Rough stone work with jelly filling	C.yd.	121

Notice dated 20th March 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M. on 15th April 1929, for constructing the Sree Vyasarayaswamy Mutt at Sosale extension, T.-Narsipur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division Mysore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 500 (five-hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the Sree Vyasarayaswamy Mutt at Sosale, T.-Narsipur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work clearly.

Abstract estimate for constructing the Sree Vyasarayaswamy Mutt at Sosale Extension, T.-Narsipur Taluk.

Sl. No.	Items of work	Per	Quantity
1	Earth work excavating foundation and filling in basement ...	Lump	sum
2	Concrete stone jelly in mortar	C.ft.	2,143
3	Burnt stone in mortar foundation and basement	,,	2,793
4	Brick in mud	,,	4,757
5	Brick in mortar (under deductions)	,,	1,000
6	Do do arch work	,,	121
7	Burnt stone slabs 6″ in mortar	S.ft.	944
8	Teakwood panelled door with iron fittings, etc., complete ...	,,	397
9	Teakwood windows with iron bars with inner glazed and outer panelled shutter complete with fittings, etc., complete.	,,	222
10	Teakwood ventilators with glazed shutters fixed in two halves...	,,	53
11	Rolled steel beam including hoisting and painting complete ..	Cwt.	9½
12	W I. trusses for a clear span 16′ including erecting and painting complete.	,,	12
13	Teakwood wrought and put up including woodoiling ...	C.ft.	211
14	Roofing with First Class Mangalore tiles over teak reepers; woodoiling and chunam borders and fixing ridge tile complete.	Sqr.	16·78
15	Terrace roof with 2 courses of flat tiles with concrete plastering top and bottom, etc., complete.	,,	15·53
16	Parapet wall 2 ft. high with pillars coping and cornice, etc., complete with plastering.	R.ft.	198
17	Cornice 9 inches deep	,,	242
18	Teakwood ornamental eave board 1″ thick with painting ...	,,	190
19	Galvanised iron ornamental eaves 12″ or cresting with painting...	,,	16
20	Teakwood finials and pendents for tiled roof ends ...	Lump	sum
21	Ridge tiles set in mortar main roof	R.ft.	45
22	Silicate painting 2 coats	Sqr.	18·64
23	Chunam plastering both inside and outside	,,	120·00
24	White washing 2 coats	,,	120·00
25	Cement pointing to basement	,,	5·00
26	Flooring with Cuddapah slabs 1½″ thick over 4 inches bed of concrete and cement pointing.	,,	21·64
27	Clearing site and levelling and sundry charges	Lump	sum

Estimate for constructing quarters for guard stable sheds for elephant and cattle and sinking wells within the compound of Sree Vyasaraya Mutt in the new extension of Sosale, T.-Narsipur Taluk :—

Serial No.	Description of work	Per	Quantity
	QUARTERS FOR GUARDS.		
1	Earthwork excavation for foundation	C.yd.	69
2	Burnt brick in mud	C.ft.	3,791
2A	Do chunam	,,	162
3	Teakwood wrought and put up	,,	89·95
4	Roofing First Class Mangalore tiles with teak reepers, etc.,	Sqr.	17·69
5	complete.		
	Ridge tiles set in mortar	R.ft.	93
6	Teakwood battened doors including chacolate painting ...	S.ft.	144
7	Do windows with iron bars painting ...	,,	48
8	Burnt stone slabs 6″ thick dressed	S.ft.	205
9	Chunam plastering	Sqr.	44·05
10	Flooring with 3″ concrete and smoothening with mortar ...	C.ft.	200
11	White washing 2 coats	Sqr.	44·05
12	Chunam border (mortar bonds) over roof (dwarf wall at gable ends.)	R.ft.	160
	CONSTRUCTING STABLES FOR FIVE HORSES.		
1	Earthwork excavation for foundation	C.yd.	22
2	Burnt brick in mud	C.ft.	1,682
3	Do mortar arch wall	,,	70
4	Jungle wood poles 3″ to 4″ thick including fixing charges for roofing.	R.ft.	668
5	Roofing with country tile with arecanut reepers and nails ...	Sqr.	7·64
6	Country ridge tiles set in mortar	R.ft.	47
7	Flooring with gravel and watering and tamping	Lump	sum
7A	Gravel tapering in front of arch ways	Lump	sum
8	Chunam plastering	Sqr.	20·25
9	White washing 2 coats	,,	20·25
10	Mortar bonds over roof	R.ft.	80
11	Stone slabs sides of arches including holes	S.ft.	60
12	Burnt stone slabs between arch ways	,,	45
	CONSTRUCTING ELEPHANT AND CAMEL SHEDS.		
1	Earthwork excavation for foundation	C.yd.	21
2	Burnt brick in mud	C.ft.	1,406
3	Roofing junglewood poles 3″ to 4″ including fixing charges, etc.	R.ft.	464
4	Bressumers junglewood	,,	26
5	Chunam plastering	Sqr.	15.73
6	White washing	,,	15·73
7	Roofing country pot tiles with arecanut reepers and nails, etc....	,,	6·68
8	Ridge country tiles set in mortar	R.ft.	30
9	Flooring 6″ with gravel watering and tamping and gravel tapering in front of entrance.	Lump	sum
10	Mortar bonds over roof, ...	R.ft.	44
11	Burnt stone slabs in front of entrance over basement ...	S.ft.	36
	CONSTRUCTING SHED FOR CATTLE.		
1	Earthwork excavation for foundation	C.yd.	17
2	Burnt brick in mud	C.ft.	849
3	Burnt stone slabs 6″ thick	S.ft.	39
4	Roofing junglewood poles 3″ x 4″ with tarring including fixing charges.	R.ft.	1,400
5	Roofing country pot tiles with arecanut reepers, nails, etc. ..	Sqr.	5·50
6	Ridge tiles set in mortar	R.ft.	27
7	Teakwood battened door with painting	S.ft.	24
7A	Do ventilators	,,	16
8	Burnt brick in mortor	C.ft.	85
9	Chunam plastering	Sqr.	11·03
10	Flooring	Lump	sum
11	Unforeseen works	Lump	sum

N. G. KRISHNA IYENGAR,
Executive Engineer.